



NOTES

1. MYCORRHIZAL INOCULANTS:
- INSTALL MYKE PRO LANDSCAPE G.
2. WATERING:
- SOAK THE ROOTBALL AND BACKFILL AREA WITH 40 LITRES OF WATER AFTER PLANTING.
3. ROOTBALL, BURLAP, TWINE:
- CUT AND REMOVE ALL WIRE, ROPE, BURLAP AND TWINE FROM THE TOP 1/3 OF THE ROOTBALL.
4. CROWN PRUNING:
- PRUNE AT PLANTING TO CAREFULLY REMOVE DEAD, BROKEN, DISEASED OR DAMAGED BRANCHES.



**PUBLIC WORKS
STANDARD DRAWING**

DATE: AUGUST 2016

APPROVED BY

DRAWN BY

G.K./B.N.

C.B.

STD. DWG. NUMBER

SCALE

5-4-5

N.T.S.

**CALIPER CONIFEROUS TREE
PLANTING DETAIL FOR SOFTSCAPE BOULEVARDS**