



**NOTES:**

1. PROVIDE PUMP DISCHARGE BOOT, GUIDE RAIL AND LIFTING DAVIT TO FACILITATE PUMP REMOVAL FROM SUMP PIT
2. DISCHARGE PIPING SHALL BE MINIMUM 50mm SCHEDULE 40 GALVANIZED STEEL. INCLUDE SUPPORTS AS REQUIRED.
3. LOCATE CONTROL PANEL OUTSIDE CONFINED SPACE IN BUILDING.



**PUBLIC WORKS  
STANDARD DRAWING**

REV. DATE: APRIL 2021

APPROVED BY  
MNB

DRAWN BY  
GM BluePlan

**SEWAGE PUMPING STATION  
DUPLEX SUMP PUMP DETAIL**

STD. DWG. NUMBER  
SPS-114

SCALE  
Not to Scale