Inglewood Wastewater Treatment Plant Upgrades and New Access Route

Public Information Centre

MAY 29th, 2017 6:30 p.m. – 8:30 p.m.

INGLEWOOD COMMUNITY CENTRE

Please Sign In



Project Background

Inglewood Wastewater Treatment Plant Facts:

- Constructed in 2004
- Owned and operated by Region of Peel

Comprehensive Review Recommendations:

- Improve wet weather reliability
- Increase process equipment standby capacity
- Construct standby equipment to ensure uninterrupted operation during power failures







Preferred Design Concept


- Retrofit the existing building with:
 - Wastewater flow monitoring
 - Screening equipment for removal of rags and large solids
 - Expanded laboratory and maintenance space
- Construct a new treatment tank
- Construct a new building with:
 - New process equipment
 - New electrical room
- New emergency power generator





New Access Route Requirement

- Existing access to the site is through a private driveway
- Causes operational concerns and is disruptive to residential area
- Region preference to develop an alternative access to the site
- A number of alternatives were developed and evaluated



(Google, 2016)



Access Route Alternative 1: MacDonald Street Not Recommended

- Private gated access owned by the Region
- Rail crossing will require additional design, permits and coordination
- Increased traffic may affect private residences on MacDonald Street
- Traffic controls required at rail crossing and across Caledon Trail
- Minor property entry (easement) requirements
- Orangeville Brampton Rail Access Group (OBRAG) has only approved a temporary construction access and will not grant approval for permanent access
- Least impact to the Caledon Trail





Access Route Alternative 2: Arena Access Options Not Recommended

- Private gated access owned by the Region
- Rail crossing not required
- Potential significant grading requirements and tree removal
- Access crosses and runs close to existing creek
- Major property entry (easement) requirements
- No impact to the Caledon Trail
- Credit Valley Conservation Authority (CVCA) will not grant approval for permanent access close to waterways





Access Route Alternative 3: Caledon Trail Access No. 1 Recommended

- Portion of the access shared with the Caledon Trail (approximately <u>320 m</u>)
- No rail crossing required
- Potential significant grading requirements and tree removal adjacent to the Caledon Trail
- Increased traffic may affect users of the Caledon Trail
 - Typically 1 vehicle required per day
- Significant coordination with the Caledon Trail
- Moderate property entry (easement) requirements
- Road separated from Caledon Trail





Access Route Alternative 4: Caledon Trail Access No. 2 Recommended


- Portion of the access shared with the Caledon Trail (approximately <u>250 m</u>)
- No rail crossing required
- Potential significant grading requirements and tree removal adjacent to the Caledon Trail
- Increased traffic may affect users of the Caledon Trail
 - Typically 1 vehicle per day
- Significant coordination with the Caledon Trail
- Moderate property entry (easement) requirements
- Road separated from Caledon Trail





Recommended Access Route Alternatives











Next Steps

Consider Public and Agency (CVC, Town of Caledon, etc.) Input Confirm Preferred Solution



Detailed Design, Property Entry Rights and Construction

Summer 2017



Fall 2017



Inglewood Water Supply System Update

- The Region identified the need to construct a new municipal water well (Well #4) to add supply capacity to the community of Inglewood and allow for decommissioning of Well #2
- Well #4 was recently completed 400m north of existing Well #3
- Well #4 will be connected to the existing treatment facility currently providing treatment for Well #3
- Connection anticipated for fall/winter 2017
- Well #2 decommissioning anticipated for 2018/2019





Have Your Say

- Fill in a comment sheet today or email your comments to the contact below by June 12th, 2017
- Contact Peel staff with your questions

Grace Krasowski, P. Eng. Project Manager, Region of Peel Grace.Krasowski@peelregion.ca



Access Route Alternatives

Alt	Alternative Access Routes	"Must-meet" Criteria			
		Reliability	Technical Feasibility	Key Differentiators	Recommendation
0	Do Nothing	X	V	 Coordination issues with private residence Increased concerns regarding potential spills on private residence 	Not recommended
1	MacDonald Street Access	Ý	V	 Private gated access owned by the Region Rail crossing will require additional drawings, designs, permits and coordination Increased traffic may effect private residences on MacDonald Street Minor property entry (easement) requirements 	Orangeville Brampton Rail Access Group (OBRAG) will not grant approval for permanent access
2	Arena Access Options	¥	~	 Access through the Lloyd Wilson Centennial Arena No rail crossing required Potential significant grading requirements Both routes run close to existing Creek and/or the Credit River Major property entry (easement) requirements 	Credit Valley Conservation Authority (CVCA) will not grant approval for permanent access close to waterways
3	Caledon Trail Access No. 1	✓	✓	 Access shared with the Caledon Trail No rail crossing required Significant coordination with Caledon Trail required. Potential significant grading requirements adjacent to Caledon Trail and tree removal Increased traffic may effect users of the Caledon Trail Moderate property entry (easement) requirements 	Recommended for further evaluation – Short-listed
4	Caledon Trail Access No. 2	√	✓	 Access shared with the Caledon Trail No rail crossing required Significant coordination with Caledon Trail required Potential significant grading requirements adjacent to Caledon Trail and tree removal Increased traffic may effect users of the Caledon Trail. Moderate property entry (easement) requirements 	Recommended for further evaluation – Short-listed

